


## 396-5888Y1

## QuickDraw Swing Down Inductor Gas Spring Retrofit Installation Instructions (MY23 and Older)

Kit Number: 606-08-100100
Kit Description: QuickDraw Swing Down Gas Spring Upgrade Kit

ITEM NO.	PART NUMBER	DESCRIPTION	QTY.
1	359-5889Y1	Gas Spring, 28" Cylinder Only, 125 lb.	1
2	359-5890Y1	Ball Socket, M8 x 1.25 thread, M13 socket	2
3	359-5891Y1	Ball Stud, 5/16" x 1" thread, M13 ball joint	2
4	323-05	5/16" Flange Nut	2



Revised: 7/10/2023





## **Pre-Drill Instructions**


## **Equipment Needed:**

- Power Drill
- Center Punch and Hammer
- 3/8" Drill Bit
- 1/2" End Wrench
- 606-08-100100 Upgrade Kit
- 1. Remove the 3/8" hardware connecting the 4130Y1 bracket to the 4083Y1 bracket. It may be necessary to remove the tank from the parallel arms for stability.
- Remove the 16" coil springs from the back of the swing down, followed by the 4079Y1 bracket and hardware.
- 3. Drill two 3/8" holes for the new gas spring: one in the 4130Y1 bracket, and one in the top parallel arm for the tank. Reference picture on page 1.
- 4. Begin by drilling the 3/8" hole in the 4130Y1 bracket on the opposite side of the latching handle. Use the center punch and hammer to mark a pilot measured 3" from the bottom of the bracket, and 3/8" from the front (reference picture). Drill hole and de-bur.
- 5. Next, drill the 3/8" hole on the top parallel arm on the opposite side of the latching handle. Use the center punch and hammer to mark a pilot measured 7-3/4" from the top of the parallel arm in line with the other holes on the side of the arm (reference picture). Drill hole and de-bur.
- 6. Proceed to install the gas spring upgrade kit as shown on page 1 of the instructions.

**NOTE:** Ensure the holes are drilled in the exact locations specified. If holes are not drilled in the correct locations the gas cylinder could fail.







Revised: 7/10/2023

Page 2 © 2023 SurePoint Ag Systems, Inc.